Sl. No.	Description of Items
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and eletri conduits either in pits or in trenches 1.5 m and above in width, in hard wo not exceedi 1.5m, in depth including dressing the bottom and sides of pits and trenches stacking t excavated soil clear from edges of excavation with lead upto 50 m after breaking of clc complete as per specification and direction of engineer in charge of the work
2	Providing and laying in position to required level or slope 300 mm internal diameter s glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar proportion of 1:1 testing of pipes and joints including cost of mateials, labour charg complete as per specification and direction of engineer in charge of the work
3	Constructing brick masonry circular type manhole 0.91 m internal dia at borttom 0.91 deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designat 50 in cement mortar 1:4 inside cement plastered 12mm thick with cement mortar finished with a floating coat of neat cement, foundation concrete M 10 using 40mm a downsize granite metal and making necessary channel in cement concrete M 50 w 20mm and downsize granite metal cover and frame (heavy duty, HD-20 grade designati 560mm internal diamter confirming IS: 12592, total weight cover and frame to be not le than 182 kg, fixed in cement concrete 1:2:4 20mm and downsize broken granite me providing and removing centering, shuttering including cost of materials, labour charg HOM of machinery complete as per specification (excavation, footrests and 12mm th cment plaster on the external surface shall be paid separately) complete as specification and direction of enginner in charge of the the work
4	Providing and constructing burnt brick masonry with approved quality of non-modular bri of standard size of class designation 50 (table moulded) with cement mortar 1:6 basement and superstructure including cost of materials, labour charges, scaffolding cur complete as per specification and direction of engineer in charge of the work
5	Providing 20mm thick cement plaster in signle coat with cement mortar 1:4 to stc masonry including rounding off corners wherever required smooth rendering : Providing a removing scaffolding including cost of materials, labour, curing complete as specification and direction of engineer in charge of the work
6	Providing & fixing SFRC Cover and frame 560mm (ID) Heavy Duty material code No-03 complete as per specification and direction of engineer in charge of the work
7	Refilling availabe earth around pipe lines, cables in layers not exceeding 20cms in de compacting each deposited layer by ramming after watering with lead upto 50m and lift u 1.5 m including cost of all labour complete as per specification and direction of engineer charge of the work
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by enginner in charge of the work lead 4 Km a) Basic rate for halage of mateirals as pe it average earrth of work 1.28 Tonne/Km for Rs. 2.00 /Km c) Add loading and unload complete as per specificaion and direction engineer in charge of the work

CERTIFICATE

1 This is to certify that the contractor has completed the work satisfactorily.
2 The contractor has cleared the debries from the work sport
3 The contractor has used his own vehicles for the coveying the debries.
4 There are no departmental issues for the above work.

ಕಂದಾಯ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಧಿಕಾರಿಗಳವರ
ಕಚೇರಿ
ಕ. ದಾಸರಹಳ್ಳಿ ಉಪ ವಿಭಾಗ
ನೈಋತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಜಾಲಹಳ್ಳಿ, ಬೆಂಗಳೂರು -560 073